700 Woodard Ave., Cleburne, Texas, 76033

ARCHITECT

W.K. HOUP, ARCHITECT, INC. 816 ROYAL TERRACE, HURST, TEXAS, 76053 CONTACT: William "Kim" Houp PHONE: 817-938-8294 E-MAIL: kimandkathy@sbcglobal.net

STRUCTURAL ENGINEER

FWN & A STRUCTURAL ENGINEERING 1015 W. BROADWAY AVE. PHONE: 817-332-1944 E-MAIL: fneal@fwna-eng.com

CONSTRUCTION MANAGER

207 N. RIDGEWAY, CLEBURNE, TEXAS, 76033

DSA, Inc. Construction Mgr.

PHONE: 817-645-8864

MPE Engineer

LARRY L. BLACKMON, INC. 6716 AZLE AVE., LAKE WORTH, TEXAS 76135 PHONE: 817-238-9801 FAX: 817-238-9804 E-MAIL: regina@blackmonconsultingengineers.com

MECHANICAL CONTRACTOR

CLEBURNE HEAT AND AIR 496 PARK ST. CLEBURNE, TEXAS, 76031 PHONE: 817-774-2471

FACILITY SQUARE FOOTAGE BREAKDOWN

TOTAL BUILDING S.F. 10,817 S.F. REMODELED AREA 8,435 S.F.

MECHANICAL / PLUMBING / ELECTRICAL M100 | MECHANICAL GENERAL NOTES / SCHEDULES P100 | PLUMBING PLAN / GENERAL NOTES / FIXTURE SCH'D. P101 | WATER DISTRIBUTION PLAN

STRUCTURAL

INDEX OF DRAWINGS

CO.1 COVER SHEET, GENERAL NOTES

A1.1 PARTIAL FINISH "SPOT GRADES"

DEMOLITION PLAN / NOTES

ENLARGED "PARTIAL" PLANS

ACCESSIBILITY DETAILS

A1.0 PARTIAL EXISTING GRADING, "SPOT GRADES"

A2.2 REFERENCE FLOOR PLAN / GENERAL NOTES

LIFE SAFETY PLAN "EGRESS" PLAN

DIMENSIONED FLOOR PLAN / GENERAL NOTES

A3.0 | ROOM FINISH SCHEDULE / SCHEDULE "KEY" / PLAN

DOOR/HARDWARE / WINDOW SCHEDULE / DETAILS

SO.1 | GENERAL NOTES / DESIGN STANDARDS / ABBREVIATIONS

NO. | DESCRIPTION

ARCHITECTURAL / CIVIL

A2.0 EXISTING FLOOR PLAN

A5.0 INTERIOR ELEVATIONS

S1.1 STRUCTURAL DETAILS

S2.1 | FRAMING PLAN / MISC. DETAILS

LEGAL DESCRIPTION

PROPERTY 70NING:

WORSHIP.....

A6.0 | REFLECTED CEILNG PLAN

AO.1 SITE PLAN

GENERAL

GENERAL NOTES / PROVISIONS

NOTE: AS DIRECTED BY THE OWNER, ANY OR ALL OF THE GENERAL PROVISIONS MAY BE REVISED OR OMITTED BY THE OWNER AND CONTRACTOR.

- THE SUBMISSION OF A BID/PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT THE CONTRACTOR/SUBCONTRACTORS HAVE FAMILARIZED THEMSELVES WITH THE PLANS. CITY ORDINANCES. FACILITY STANDARDS, AND EXISTING CONDITIONS AT THE SITE. 1.1. CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BID.
 - 1.2. REFER TO "BID DOCUMENTS" FOR SITE "WALK-THRU", DATE AND TIME TO BE ESTABLISHED BY THE CONSTRUCTION MGR.
- PRIOR TO START OF THE CONSTRUCTION. CONTRACTOR AND SUB-CONTRACTORS SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION OF ANY ITEM SHALL BEGIN UNTIL THE CONTRACTOR/SUBCONTRACTOR HAVE RECEIVED ALL PLANS AND ANY OTHER DOCUMENTATION FROM ALL OF THE PERMITTIING, AND ANY OTHER REGULATORY AUTHORITIES. FAILURE OF THE CONTRACTOR/SUBCONTRACTOR TO FOLLOW THIS PROCEDURE SHALL CAUSE THE CONTRACTOR TO ASSUME FULL RESPONSIBILITY FOR ANY SUBSEQUENT MODIFICATION OF THE "WORK" MANDATED BY ANY REQULATORY AUTHORITY.
- SHOP DRAWINGS AND SAMPLES (AS APPLICABLE) SHALL BE SUBMITTED TO THE OWNER AND CONSTRUCTION MGR. FOR APPROVAL FOR THE FOLLOWING ITEMS TO INCLUDE, BUT NOT LIMITED TOO: (ALL COLORS TO BE SELECTED BY OWNER)

FLOORING: REFER TO ROOM FINISH "KEY"SHEET A3.0; LUXURY VINYL FLOORING, CARPET SQUARES, AND CERAMIC TILE

DOOR/WINDOW FRAMES AND HARDWARE TOILET ACCESSORIES MILLWORK "SHOP" DRAWINGS. LIGHT FIXTURES PLUMBING FIXTURES AND FITTINGS METAL STAIRS HANDRAILS AND GUARDRAILS

- ALL WORK SHALL COMPLY WITH APPLICABLE STATE AND LOCAL CODES AND ALL NECESSARY LICENSES AND PERMITS SHALL BE OBTAINED BY THE CONTRACTOR AT HIS EXPENSE UNLESS PREVIOUSLY OBTAINED BY THE OWNER.
- 5. ALL WORK SHALL BE PERFORMED IN A FINISHED AND WORKMANLIKE MANNER TO THE ENTIRE SATISFACTION OF THE OWNER AND IN ACCORDANCE WITH THE BEST RECOGNIZED TRADE PRACTICES. 6. THE CONTRACTOR/SUB-CONRACTORS SHALL BE RESPONSIBLE FOR
- VERIFICATION OF ALL UTILITIES REQUIRED FOR THE "WORK" AND WITHIN THE SCOPE OF THE WORK. . UPON REVIEW OF THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY
- THE ARCHITECT OF ANY DISCREPANCIES AND/OR OMISSIONS PRIOR TO START OF CONSTRUCTION. 8. CONTRACTOR SHALL PROVIDE A MINIMUM OF TWO, (2), TYPE 'ABC' FIRE EXTINGUISHERS AND ADDITIONAL PROTECTION, AS NECESSARY,
- TEXAS ORDINANCES AND FIRE DEPARTMENT REGULATIONS. 9. ALL PARTITIONS SHALL BE CAPABLE OF SUPPORTING A UNIFORM LATERAL LOAD OF 5 PSI OR GREATER AS AS PER CODE.

DURING CONSTRUCTION, AS REQUIRED BY THE CITY OF CLEBURNE,

- CONSTRUCTION MANAGER SHALL COORDINATE ALL DELIVERIES OF BUILDIING EQUIPMENT AND MATERIALS, TO THE SITE OR OFF SITE, MATERIALS CERTIFICATION INDICATING THE "OWNER" AS THE BENEFICARY OF THE POLICY.
- CONTRACTOR SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT. AND FIXTURES, AND SERVICE REQUIRED FOR THE PROPER EXECUTION OF THE "WORK" AS SHOWN.
- 12. CONTRACTOR SHALL SUPERVISE THE "WORK" AND COORDINATE ALL
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR THE ACTS OF OMISSIONS OF EMPLOYEES AND SUB-CONTRACTORS. 14. MATERIALS AND EQUIPMENT INCORPORATED IN THE "WORK" SHALL
- BE NEW, GOOD QUALITY, AND FREE FROM DEFECTS. 15. CONTRACTOR AND SUB-CONTRACTS SHALL WARRANTY ALL WORK FOR ONE (1) YEAR FROM THE DATE OF THE "CERTIFICATE OF
- 16. CONTRACTOR/SUBCONTRACTORS SHALL PROVIDE A "CERTIFICATE OF INSURANCE" PRIOR TO START OF "WORK". IN ACCORDANCE WITH OWNER'S REQUEST.
- 17. CONTRACTOR/SUB-CONTRACTORS SHALL BE RESPONSIBLE FOR THE PROTECTION OF "WORK" DAMAGED FOR ANY REASON AND SHALL REPLACE AT NO ADDITIONAL COST TO THE OWNER.
- 18. REVISIONS, CHANGES, OR SUBSTITUTIONS MAY BE PERMITTED IF ITEMS ARE SUBMITTED TO THE OWNER IN A TIMELY MANNER, IN WRITING, AND APPROVED BY THE OWNER IN WRITING AND THE CITY OF HURST, TEXAS. CONTRACTOR/SUBCONTRACTOR SHALL BE RESPONSIBLE/LIABLE FOR REPLACEMENT OF UNAUTHORIZED SUBSTITUTIONS NOT "APPROVED", AS NOTED. THE OWNER RESERVES THE RIGHT TO REJECT SUBMITTED SUBSTITUTIONS
- 19. ALL GLAZING SHALL BE TEMPERED AND/OR SAFETY GLAZING TO CONFORM TO LOCAL CODES/ORDINANCES, 2015 IBC, CHAPTER 24 AND IN ACCORDANCE WITH THE RESIDENTIAL IECC. REFER TO WINDOW SCHEDULE SHEET A4.0.
- 20. ELECTRICAL CONTRACTOR SHALL PROVIDE ALL POWER REQUIREMENTS FOR EACH PIECE OF EQUIPMENT FURNISHED BY THE OWNER. ALL ELECTRIC WORK SHALL BE INSTALLED IN ACCORDANCE WITH NEC AND LOCAL ORDINANCES.
- 21. ALL CONCRETE SHALL BE 3,500 PSI AT 28 DAYS COMPRESSIVE STRENGTH WITH A MAXIMUM SLUMP OF FOUR INCHES (4") UNLESS NOTED OTHERWISE. REFER TO AND COORDINATE WITH STRUCTURAL DOCUMENTS.
- 22. ALL FRAMING SHALL BE DONE IN ACCORDANCE WITH CHAPTER 23, OF THE INTERNATIONAL BUILDING CODE. REFER TO AND COORDINATE WITH STRUCTURAL DOCUMENTS.
- 23. CONTRACTOR/SUB-CONTRACTORS SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT ADJACENT PROPERTY DURING CONSTRUCTION IN ACCORDANCE WITH THE CITY OF HURST, TEXAS, CODES AND ORDINANCES. CONTRACTOR SHALL ALSO PROVIDE PROTECTION OF PEDESTRIANS, IN ACCORDANCE WITH THE CITY OF HURST, TEXAS, CODES, AND ORDINANCES, INCLUDING COMPLIANCE WITH IBC CHAPTER 33 AND SECTION 3306, "PROTECTION OF PEDESTRIANS.

24. CONTRACTOR/SUBCONTRACTORS SHALL KEEP THE "AREA OF WORK' THE PROJECT SITE, CLEAN AND FREE FROM THE ACCUMULATION OF DEBRIS AND WASTE AND SHALL REMOVE "DEBRIS AND WASTE" FROM THE SITE IN ACCORDANCE WITH THE CITY OF CLEBURNE, TX REQUIREMENTS AND ORDINANCES AND AS REQUIRED BY THE

25. CONTRACTOR SHALL ASSEMBLE, IN 3-RING BINDERS, AND PRESENT

TO THE OWNER, ALL LABOR AND MATERIALS WARRANTIES, AND ALL "LABOR AND MATERIALS" LIEN RELEASES PRIOR TO "FINAL"PAYMENT OF "RETAINAGE" PREVIOUSLY HELD.

FACILITY MANAGER AND SECURITY PERSONNEL.

- 26. ALL FIRE EXTINGUISHERS SHALL BE; 5LB, ABC, MULTIPURPOSE, FIRE EXTINGUSHERS AS SHOWN.
- 27. PROTRUDING OBJECTS SHALL COMPLY WITH IBC, SECTION 1003.3 THROUGH SECTION 1003.5.
- 28. ALL INTERIOR FINISHES SHALL COMPLY WITH IBC CHAPTER 8, INTERIOR FINISHES, SECTION 803.1.1, INTERIOR WALL AND CEILING FINISH MATERIALS, CLASSIFIED IN ACCORDANCE WITH ASTM E 84 REFER TO TABLE 803.11, INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY.
- 29. CONCEALED INSULATION IN WALLS AND CEILINGS TO HAVE A FLAME SPREA INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPE INDEX OF MORE THAN 450. CODE REFERENCE 720.2.
- 30. TO THE GREATEST EXTENT POSSIBLE ALL MATERIALS SHALL COME FROM LOCAL VENDORS LOCATED WITHIN 100 MILES OF THE SITE.
- 31. TEXAS ACCESSIBILITY STANDARDS; OWNER / CONTRACTOR SHALL BE RESPONSIBLE FOR "PROJECT REGISTRATION, IF REQUIRED, BY THE TEXAS DEPARTMENT OF LICENSING AND REQULATION.
- 32. PAYMENTS TO CONTRACTOR
- 31.1 PAYMENTS TO THE CONTRACTOR SHALL BE IN STRICT ACCORDANCE WITH THE TERMS SET FORTH IN THE AGREED CONTRACT WITH THE OWNER AND CONSTRUCTION MANAGER.
- 31.2 VERIFICATION OF "REQUEST FOR PAYMENT" AND "PERCENTAGE OF WORK COMPLETED", SHALL BE PERFORMED, IF REQUESTED BY THE OWNER, BY THE ARCHITECT OR AS AGREED UPON BY THE OWNER AND CONSTRUCTION MGR.

OWNER

CALVARY BAPTIST CHURCH 700 WOODARD AVE. CLEBURNE, TEXAS. 76033

Owner's Representitive;

KERY WILLIAMS DSA, Inc. Contruction Manager 207 N. Ridgeway Cleburne, Texas, 76033

CODE ANALYSIS

817-645-8864

2015 INTERNATIONAL BUILDING CODE

2015 INTERNATIONAL COMMERCIAL ENERGY CONSERVATION CODE, IECC

2015 INTERNATIONAL PLUMBING CODE 2015 INTERNATIONAL MECHANICAL CODE

2015 INTERNATIONAL FIRE CODE 2017 INTERNATIONAL ELECTRICAL CODE

"SCOPE OF WORK" 🛆

INTERIOR RENOVATION; TOILET RENOVATIONS TO COMPLY WITH "TEXAS ACCESSIBILITY STANDARDS" ENLARGE PARTITION OPENINGS TO RECEIVE NEW 3'-0" WIDE, AND 'HARDWARE" TO COMPLY WITH T.A.S. REQUIREMENTS. REPLACE AUDITORIUM HVAC EQUIPMENT, REFER TO ELECTRICAL DOCUMENTS FOR NEW LIGHTING LAYOUT, AND "EXIT" FOXTURES. REPLACE "LAY-IN" ACOUSTIC TILE CEILING AND "LED" LIGHT FIXTURES, TAPE, BED, TEXTURE ALL NEW AND DAMAGED GYPSUM BOARD. REPLACE FLOORING, CARPET, LUXERY VINYL TILE, AND BASE. NEW "SOUND EQUIMENT AND SYSTEM, (SUB-CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR APPROVAL BY OWNER) RESTRIPE PARKING ADJACENT TO FACILITY, REFER TO SHEET A.1.1.

EXTERIOR RENOVATION: WALKS AND RAMPS TO COMPLY WITH "TEXAS ACCESSIBILITY STANDARDS" AND REQUIREMENTS FOR "ACCESSIBLE ROUTES".

NOTES:

THE INTENT OF THE "SCOPE OF WORK" IS TO GIVE AN GENERAL OVERVIEW OF THE PROJECT, AND NOT TO BE CONSTRUED AS A "DETAILED" ITEMIZED LIST OF WORK.

THE SUBMISSION OF A BID/PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT THE CONTRACTOR/SUBCONTRACTORS HAVE FAMILARIZED THEMSELVES WITH THE PLANS, CITY ORDINANCES, FACILITY STANDARDS, AND EXISTING CONDITIONS AT THE SITE. THE CONSTRUCTION MANAGER SHALL SET THE TIME/DATE OF A PRE-BID (ON-SITE) MEETING TO WALK THE PROJECT.

SF "SINGLE FAMILY"

E100 | ELECTRICAL POWER PLAN / FIXTURE SCHEDULE E101 | ELECTRICAL LIGHTING PLAN / FIXTURE SCHEDULE

CALVARY BAPTIST CHURCH, CLEBURNE FACILITY, TEXAS

700 WOODWAY AVE. CLEBURNE, TEXAS, 76033

5.581 ACRES OF LAND IN THE THOMAS HARLOW SURVEY


ABSTRACT NO. 335, CITY OF CLEBURNE,

JOHNSON COUNTY, TEXAS

OCCUPANCY CLASSIFICATION ASSEMBLE GROUP A-3 REFERENCE CHAPTER 3, SECTION 303.4

OCCUPANCIES INCLUDING ASSEMBLY USES INTENDED FOR





OCCUPANCY GROUP: A-3 CONSTRUCTION TYPE: TYPE-VB wkh

MOIL \mathbf{m}

0 Y

Proj. no. 21001 Drawn by: KH Date: 08.03.22 Revision Number

08.05.22

Sheet no.